Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of work: Improvements to Roads And Drains At SFS 707 And Surrounding Area in Ward No 03

Modified Schedule - B

Sl No	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
1	KSRRB 300-2. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications	Cum	956.60	220.00	Rupees Two Hundred Twenty Only
	Above125%	Cum	151.37	204.77	#NAME?
2	KSRB 4-2.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 280kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 25 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	138.80	5500.00	Rupees Five Thousand Five Hundred Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 2500, 2700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Cum	272.27	5640.00	Rupees Five Thousand Six Hundred Forty Only
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications.	Tn	18.02	75700.00	Rupees Seventy Five Thousand Seven Hundred Only
5	Providing and Fixing pre cast covering Slab 100mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)	Sqm	409.08	2550.00	Rupees Two Thousand Five Hundred Fifty Only

	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
	Sliding and fixing RCC precast cover slab of 250mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	18.00	5700.00	Rupees Five Thousand Seven Hundred Only
	Above125%	Sqm	9.81	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Executive Engineer,
B.Bannerghatta Division
BBMP Bangalore